



September 8, 2025

# Champlain Towers South Collapse Investigation

Matthew Fadden, PhD, PE  
*Managing Director and Principal  
Walter P Moore Associates, Inc.*

Gary Klein, PE, SE  
*Vice President and Senior Principal  
Wiss, Janney, Elstner Associates, Inc.*

---

# Presentation Outline


## 1. Champlain Towers South Collapse

Document Review

Site Investigation

Laboratory Studies

Structural Analyses



Collapse Theory



## 2. State of Structural Assessments in Florida


# Findings & Observations

## *Document Review*





## What we knew June 24, 2021 – Surfside, FL



- A building had partially collapsed at ~1:30 am
- 100+ people were feared missing or dead
- The cause was unclear
- Initial information via:
  - Social media
  - News
  - Photos
  - Videos



## Building Description


- 12-story L-shaped structure with 136 units built in 1981
- Reinforced concrete flat plate construction
- Parking on the lobby level and the basement garage
- Pool deck terrace on the south side of the buildings



---

## Codes and Design Standards (1981)

- South Florida Building Code 1979
- ACI 318-77: Building Code Requirements for Reinforced Concrete








Atlantic Ocean



North



Collins Ave.




Atlantic Ocean

---

## 1996 Retrofit: Pool Deck & Garage

Under the supervision of a licensed Florida professional engineer, a repair contractor performed:

- Planter waterproofing
- Paver installation
- Concrete structural repairs



March 22, 1996

Thomas Conway  
Building Manager  
Town of Surfside  
9293 Harding Avenue  
Surfside, FL 33154

Dear Mr. Conway,

██████████ will be starting a project at Champlain Towers South located at 8777 Collins Avenue, Surfside FL. Included in the scope of work will be concrete structural repair in the parking garage. This type of repair entails removing loose concrete overhead, treating steel rebar with rust inhibitive coating and patching back with repair mortar. Also included in the garage will be urethane foam injection in ceiling cracks (approximately 500 lineal ft.).

The condo has retained the services of ██████████ 5100 West Copans Road, Margate, FL 33063 to do the inspections and supervise the project.

Please feel free to contact me with any questions.

Sincerely,

██████████  
Sales Manager

---

## 2018 Recertification Report

- Abundant cracking and spalling in garage with calcium carbonate leaching
- Previous repairs failing due to poor workmanship
- Concrete repair recommended following standard practices
- Recommend that the entrance and pool decks slabs showing distress be removed and replaced



Figure J1: Typical cracking and spalling at parking garage columns



Figure J2: Spalling with exposed steel reinforcement at topside of garage deck.




## Recertification Investigation – Deck Finish




# Recertification Investigation – Concrete Core Samples

Parking Deck




Pool Deck



Excessive Cover


## Recertification Investigation - Planters





# Recertification Engineer Calculations


- Recertification engineer analyzed the slab along Column Line T
- Punching shear results were exceeded in every calculation iteration.



**2.11.2. Punching Shear Results**

Support	$V_u$ kip	$v_u$ psi	$M_{unb}$ k-ft	Comb	Patt	$\gamma_v$	$v_u$ psi	$\Phi V_c$ psi
1	80.05	31.9	195.51	U1	All	0.117	343.7	101.5 *EXCEEDED
2	202.56	236.6	10.47	U1	All	0.415	244.8	189.7 *EXCEEDED
3	133.15	183.2	-39.19	U1	All	0.422	217.6	189.7 *EXCEEDED
4	164.83	192.5	12.83	U1	All	0.375	200.5	189.7 *EXCEEDED
5	176.45	206.1	-18.39	U1	All	0.415	217.8	189.7 *EXCEEDED
6	133.61	183.9	6.98	U1	All	0.422	190.0	189.7 *EXCEEDED
7	156.94	216.0	6.70	U1	All	0.422	221.8	189.7 *EXCEEDED
8	146.79	171.5	-25.71	U1	All	0.375	191.2	189.7 *EXCEEDED
9	178.11	180.7	16.77	U1	All	0.380	190.3	189.7 *EXCEEDED
10	77.04	30.7	-172.04	U1	All	0.117	299.8	101.5 *EXCEEDED

## L13.1 Slab/Column Distress – Nov. 13, 2020




## K13.1 Slab/Planter Distress - June 2, 2021





## Garage Walkthrough Video



---

1:18 AM - TikTok Video




---

## ~1:15-1:22 AM - Unit 711 Ring Video





## Resident Observations



Unit 711

Ring Video

Unit 611

Cracks in Walls

Unit 111

12:30 am:  
Construction Noises  
1:10-1:15 am:  
Pool Deck Collapse



**Collapse Timeline**  
**June 24, 2021**

1	1:10– 1:15 AM	Pool Deck
7 – 12 minutes		
2	1:22 AM	East Tower South
3	+ 3 seconds	East Tower North
4	+ 8 seconds	East Tower East
5	West portion does not collapse	





# Findings & Observations

## *Site Investigation*




## Collapse Site – October 2021

---



## Basement Slab Survey - Topography






## Collapse Site Sampling




## NIST/NCST - Primary Evidence Facility





## Primary Evidence Facility – North Bay\*





## Primary Evidence Facility – South Bay

Majority of Items from  
Collapsed Portion

Item 119  
Item 128  
Item 68  
Item 999





Majority of Items from  
Imploded Portion



## Primary Evidence Facility – Item 344 "Punched Slab"




## PEF – Item 299 "Beam A"





## Primary Evidence Facility – Item 341 - 16x16 Column




# Findings & Observations

## *Laboratory Studies*



## Concrete Petrography and Testing




### Basement Slab Samples

- Concrete typical to Florida
  - Moderate w/c ratio (0.35-0.45)
  - Well mixed
  - Non-air entrained
- Corrosion consistent with that at concrete placement
- Low chlorides and carbonation




## Concrete Material Properties

Location	Average Compressive Strength psi (MPa)	Min. Specified Compressive Strength psi (MPa)
Transfer Girder	3560 (25)	4000 (28)
Column M15.1	3785 (26)	6000 (41)
Column Q8	5820 (40)	6000 (41)
Pool Deck	4475 (31)	4000 (28)
Perimeter Wall	4280 (30)	4000 (28)
Shear Wall East	6600 (46)	6000 (41)
Shear Wall West	8155 (56)	6000 (41)



## Steel Reinforcement



	Min. Specified (ASTM 615 Gr. 60)	Perimeter Wall (avg.)	Pool Deck (avg.)
Yield – $F_y$ : psi (MPa)	60,000 (414)	69,948 (482)	77,012 (531)
Ultimate – $F_u$ : psi (MPa)	90,000 (621)	106,814 (736)	110,300 (760)
Elongation (%)	7-9 depending on bar size	12.4	12.9


# Findings & Observations

## *Structural Analysis*







## Punching Shear Failures



## Pool Deck Slab Distress





# Punching Shear




- Punching Shear
  - Dependent on slab depth and concrete strength
  - $V_c = 4\sqrt{f'_c}b_o d$
- Current research shows that:
  - Dependent on flexural reinforcement and slab thickness
  - A coefficient of 4 may be unconservative for low reinforcement ratios




## Full Building – Finite Element Model



## Pool Deck – At Collapse



## Pool Deck – At Collapse





---

## Pool Deck Punching Shear (Column K 13.1)

$$3\sqrt{f'_c}$$

As Designed (safety factor)	K 13.1
Size (in x in)	16x12
Nominal $f'_c$ (psi)	4000
Clear Cover (in)	0.75
Factored Load (kip)	266
Reduced Nominal Capacity (kip)	155
<b>Demand to Capacity Ratio</b>	<b>1.72</b>


At Collapse (no safety factor)	K 13.1
Size (in x in)	16x12
Estimated $f'_c$ (psi)	5000
Clear Cover (in)	2.13
Estimated Load (D) (kip)	128
Nominal Capacity (kip)	150
<b>Demand to Capacity Ratio</b>	<b>0.85</b>

Demand to Capacity Ratio  $> 1$  = **BAD**

Demand to Capacity Ratio  $< 1$  = **GOOD**

# Lobby Level Slab – Finite Element Model

As-Designed Positive Bending,  $1.4D+1.7L$ ,  $\Phi = 0.85$




# Collapse Theory







## Pool Deck/Lobby Level




## Slab Elevations



# Collapse Hypothesis



Before April 13, 2020






# Collapse Hypothesis

After April 13, 2020 and Before June 2, 2021




# Collapse Hypothesis

June 24, 2021: 1:10 – 1:15 AM



# Collapse Hypothesis


June 24, 2021: 1:10 – 1:15 AM






# Collapse Hypothesis

June 24, 2021: 1:10 – 1:15 AM




# Progressive Collapse Mechanism



# Collapse Hypothesis

June 24, 2021: 1:22 AM





# Collapse Summary



---

## Mistakes that Appear to have Contributed

### Inadequate design of pool deck slab

- Especially punching shear

### Excess weight on pool deck

- Original concrete overlay not shown on drawings
- Addition of pavers
- Larger planters than shown on design drawings

### Shallow top reinforcement

- Decreasing punching shear strength

### Engineers responsible for repairs failed to identify the deficiency

## Other Potential Contributing Causes

- Long-term sustained load effects
- Low top flexural reinforcement ratio
  - Code now requires more reinforcement
- Significance unclear
  - Water buildup in planters
  - Corrosion



# Judge gives final approval to 'remarkable' \$1 billion Surfside condo collapse settlement

BY LINDA ROBERTSON

UPDATED JUNE 24, 2022 8:48 AM






# State of Structural Investigations in Florida



---

## Current Status in Florida

- Miami-Dade/Broward have had structural “Recertification”
- Statewide adoption of “Recertification” (SB-4D and SB 154) after Champlain Towers Collapse.
- Affects all condominiums 3 stories and higher
- Thousands of buildings, ~900,000 units over 30 years old
- This is spreading to other states...



---

## What is Safe?

**Substantial Structural Deterioration.** Means a condition that negatively affects a building's structural condition and integrity or a major structural component whose condition meets the definition of Dangerous. The term does not include surface imperfections such as cracks, distortion, sagging, deflections, misalignment, signs of leakage, or peeling of finishes unless the licensed engineer or architect performing the phase one or phase two inspection determines that such surface imperfections are a sign of substantial structural deterioration.



developed by WJE to meet the requirements of the City of Miami for the recertification inspection for the subject building. **The subject building is structurally safe for its use and present occupancy.** If you have any questions or require additional information, please reach out to us.



*"As a routine matter, in order to avoid possible misunderstanding, nothing in this report should guarantee for any portion of the structure. To the best of my knowledge and ability, this report represents an accurate appraisal of the present condition of the building based upon careful evaluation of observed conditions to the extent reasonably possible."*

# Recertification Requirement

- Inspections are:
  - Prescriptive
  - Visual-only
  - Limited to observable distress
- Design deficiencies are undetectable without distress manifestation
- Examples
  - Example 1. Actual structural distress is often missed
  - Example 2. Perceived distress can lead to premature recommendations
  - Example 3. Maintenance/non-structural upgrades are often imposed on owners



REGULATORY AND ECONOMIC RESOURCES DEPARTMENT  
11805 SW 26<sup>th</sup> Street, Miami, Florida 33175  
786-315-2000  
Miami-dade.gov/building

## MINIMUM INSPECTION PROCEDURAL GUIDELINES FOR BUILDING STRUCTURAL RECERTIFICATION

CASE REFERENCE NUMBER:	LICENSEE NAME:
	TITLE:
JURISDICTION NAME:	ADDRESS:
	SIGNATURE:

\*Use separate sheets for additional responses by referencing the report number.

<b>1. DESCRIPTION OF BUILDING</b>	
a. Name on Title:	
b. Building Street Address:	Bldg. #:
c. Legal Description:	Attached: <input type="checkbox"/>
d. Owner's Name:	
e. Owner's Mailing Address:	
f. Folio Number of Property on which Building is Located:	
g. Building Code Occupancy Classification:	
h. Present Use:	
i. General Description of building (overall description, structural systems, special features):	
j. Number of Stories:	k. Is this a Threshold Building as per 553.71(12) F.S. (Yes/No):
l. Provide an aerial of the property identifying the building being certified on a separate sheet. Attached: <input type="checkbox"/>	
m. Additional Comments:	



## Example 1 - Early 1970's Beam With Shear Cracking

- Noted by engineer related to the
  - Already cast concrete re
  - Original re
- Engineer's un department l of beams
  - No analysis
  - Displacem
- Association issue due to



## Slide 64

---

**CB1** displacement of over 100 family  
Calderone, Brian, 2024-05-29T15:35:55.881

**CB2** an unnecessary  
Calderone, Brian, 2024-05-29T15:37:07.993

## Examples 2 - Late 1970s Building With Excessive Column Tie Spacing

- During extensive structural maintenance CB2 work related to an ongoing recertification
- Tie spacing in columns CB1 was found to be greater than the current code-prescribed minimums
  - Invasive and unsubstantiated investigation
- Engineer drafted a letter recommending conditional occupancy without a proper analysis or understanding of the significance CB3
- Column tie spacing has a minor effect on columns dominated by axial loads (<5% of capacity) CB4



## Slide 65

---


- CB1**      current  
Calderone, Brian, 2024-05-29T15:38:30.820
- CB2**      invasive and at time unsubstantiated  
Calderone, Brian, 2024-05-29T15:38:57.462
- CB3**      without understanding or substantiating the significance (or lack thereof) of the condition identified.  
Calderone, Brian, 2024-05-29T15:42:08.203
- CB4**      As most columns do, these column had substantial ritual capacity (as built D/C well below 1.0), meaning this slight reduction in capacity had no significant impact on the column's ability to carry minimum code loads, and no action was required.  
Calderone, Brian, 2024-05-29T15:57:53.864



---

### Example 3 – Excessive Maintenance Level Upgrades

- 40-year assessment noted maintenance level distress; the engineer required \$ 30 M+ maintenance upgrades
  - No structural deficiencies, laboratory CB1 evaluation, or analysis conducted
- Engineers cannot mandate work
  - CB2 Waterproofing can alter the architectural characteristics
  - Significant upfront costs burden owners
  - Some owners may prefer architectural considerations over maintenance-level performance



## Slide 66


---

- CB1** without identifying any conditions that currently fail to meet the applicable building code requirements.  
Calderone, Brian, 2024-05-29T16:00:14.009
- CB2** While buildings generally need to be maintained,  
Calderone, Brian, 2024-05-29T16:01:01.073
- CB3** Recommending repair options and requiring repairs are not the same thing.  
Calderone, Brian, 2024-05-29T16:01:46.809

---

## We must recognize that engineers:

- Can fail to recognize the significance of observed distress
  - Future standards and guides should promote critical thinking
- Do “drive-by” assessments to get
  - Maintenance-level repair
  - Construction inspections and administration work
- Owners do not always understand the statutory requirements of the codes/standards
  - Engineers should protect owners from unnecessary and costly repairs
  - Best practice ≠ Required
  - Substantiate the need for structural repairs/retrofit appropriately



---

## Most Importantly

- Educate the general public to understand:

Structural Repairs  $\neq$  Maintenance

Maintenance = Best Practice

- No practical assessment can certify that a building is free of structural deficiencies or “safe”

What is Safe Enough?



---

## Acknowledgements

- **Akerman LLP:** Michael Goldberg and Brenda Radmacher
- **James River Insurance/Clyde and Co.**
- **Wiss Janney Elstner Associates, Inc.**
  - Gary Klein, PE, SE
- **WJE staff from South Florida and 9 other offices:**
  - Field investigation
  - Document review
  - Structural modeling and review
  - Geotechnical consulting



**walter  
p moore**

# Thank You